



NOTES:

1. ALL CONCRETE IS FILL CONCRETE.
2. TO BE 12" MIN. OR AS RECOMMENDED BY HYDRANT MANUFACTURER.
3. COVER STONE WITH 8-MIL POLYETHYLENE BEFORE BACKFILLING.
4. HYDRANT LEAD PIPE TO BE SAME MATERIAL AS WATER MAIN PIPE.
5. CONCRETE COLLAR SHALL BE FLUSH WITH GROUND IN RURAL AREAS, AND 8" BELOW FINISH GRADE IN RESIDENTIAL AREAS.

CITY OF NEW PHILADELPHIA

FIRE HYDRANT ASSEMBLY
WITH VALVE AND VALVE BOX

STANDARD
CONSTRUCTION
DRAWING NO.

SD-133

REV. 08-98